

BID SCHEDULE

Bidders Please Note: Before completing the Bid Schedule and Preparing the Proposal, carefully read "**Invitation to Bid**" and "**Notice to Bidders**", "**Instructions to Bidders**", "**Section 102 and Section 103**" of the Special Provisions of the Specifications.

The bidder shall state (in ink or type written) the bid price in words per unit measurement in the space provided in the Bid Schedule for every item for which a quantity is given.

The bidder shall also insert a unit bid price opposite each pay item name for which an estimated quantity appears in the Bid Schedule. A unit bid price is not to be entered nor tendered for any pay item for which no estimated quantity appears. Whenever a contingent amount is shown for any item in the **Bid Schedule**, such amount shall govern and be included in the bid total.

Basis of award of the bid shall be as described in Notice to Bidders, Instructions to Bidders, and Section 102 of the Special Provisions of the Specifications.

Pay Item Number bold ***Italics*** denote Major Item. (See Subsection 109.06 – Pricing of Adjustments)

BID SCHEDULE

Beach Road & Microbeach Road Intersection Improvement (Roundabout), Saipan

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
11001	Force Account Work, at <i>Fifty Thousand U.S. Dollars</i>	Contingent Sum	1	\$50,000.00	\$50,000.00
15201	Construction Survey and Staking, at	Lump Sum	1		
15701	Soil Erosion Control, at	Each	1		
20303	Removal of Structures and Obstruction (Regardless of its type as indicated on the drawing), at	Lump Sum	1		
20401	Roadway Excavation, at	Cubic Yard	1450		
30102(A)	Coral Aggregate Base Course 8-inch depth compacted, at	Square Yard	2010		
SUB-TOTAL					\$

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
30102(B)	Coral Aggregate Sub-Base Course 16-inch depth compacted, at	Square Yard	2010		
40201	Hot Asphalt Concrete Pavement 3-inch thick reinforced with FORTA-FI, Class "A" Grading "C" Type IV	Square Yard	2010		
406A01	Dense Graded Anti-Skid Asphalt Pavement, 1-inch thick reinforced with FORTA-FI, Grading "E"	Square Yard	2010		
41103	Asphalt Prime Coat, Grade SS-1H, at	Square Yard	2010		
41201	Asphalt Tack Coat, Grade SS-1H, at	Square Yard	2010		
60104	Concrete Bench with Reinforcement and base preparation	Linear Foot	265		
60105	Concrete Latte Stone with reinforcement and base preparation	Lump Sum	1		
60106	Concrete AMP Entrance Sign Board, Install Complete	Lump Sum	1		
60201	12-inch diameter HDPE Corrugated Pipe, Type S, N-12, installed complete, at	Linear Foot	60		
60221	5 feet wide x 3 feet deep Single Barrel Reinforced Concrete Box Culvert, installed complete, at	Linear Foot	40		
60402	Catch Basin with grating & Frame, complete in place	Each	2		
SUB-TOTAL					\$

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
60801	Concrete swale, 4-inch thick, complete in-place, at	Square Yard	40		
60901(A)	Portland Cement Concrete Rolled Curb, 6-inch depth, in place, at	Linear Foot	200		
60901(B)	Portland Cement Concrete Curb, 6-inch depth, in place, at	Linear Foot	135		
60901(C)	Portland Cement Concrete Curb, 12-inch depth, in place, at	Linear Foot	145		
60901(D)	Portland Cement Concrete Curb, 24-inch depth, in place, at	Linear Foot	260		
60902	Portland Cement Concrete Curb & Gutter, 12-inch depth, in place, at	Linear Foot	600		
61108	Adjustment of water gate valve cover, complete, at	Each	3		
61501(A)	Concrete Walkway, variable width, including base preparation, at	Square Yard	510		
61501(B)	Concrete Walkway, 10 feet wide, including base preparation, at	Square Yard	450		
61503	Portland Cement Concrete median 6-inch high, including curb and base preparation, complete at	Square Yard	70		
61504	Concrete Ramp with Reinforcement and Base Preparation, complete at	Square Yard	50		
SUB-TOTAL					\$

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
61509	Tact Tile Detectable Warning Device, ADA, (2'-0 x4'-0), complete at	Each	8		
62035	6"x9" Hard Stone Dark Brown Bricks, at	Square Yard	480		
62401	Furnish Top Soil, at	Cubic Yard	70		
62502	Turf Establishment, at	Square Yard	160		
62632	Planting, Ixora Coccinea Plants, at	Lumpsum	1		
63301(A)	Traffic Sign, Type 1A, Single Panel, Installed complete-in-place, at	Each	15		
63301(B)	Traffic Sign, Type 1B, Multiple Panel, Installed complete-in-place, at	Each	12		
63401(A)	Pavement Marking, Type H, 4-inch wide, White or Yellow, at	Linear Foot	3850		
63401(B)	Pavement Marking, Type H, 8-inch wide, White or Yellow, at	Linear Foot	300		
63401(A)	Pavement Marking, Type H, 12-inch wide, White or Yellow, at	Linear Foot	250		
63401(A)	Pavement Marking, Type H, 24-inch wide, White or Yellow, at	Linear Foot	230		
63405(A)	Pavement Marking, Type H, Combination Arrow White, at	Each	3		
SUB-TOTAL					\$

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
63405(B)	Pavement Marking, Type H, Curve Arrow White, at	Each	1		
63405(E)	Pavement Marking, Type H, Yield White, at	Each	13		
63410(A)	Pavement Marking, Type "YY", at	Each	305		
63410(B)	Pavement Marking, Type "CC", at	Each	15		
63410(C)	Pavement Marking, Type "CR", at	Each	28		
63501	Temporary Traffic Control, at	Lump Sum	1		
63624(A)	Solar Powered Flood Light LED Lamp (Outdoor), at	Each	7		
63624(B)	Concrete Bollard with Solar Powered Wall Mounted LED Light (Outdoor), at	Each	30		
63624(C)	Solar Powered Wall Mounted LED Light (Outdoor), Installed at	Each	8		
64701	Archaeological Work Plan, Testing and Report of Findings, Complete, at	Lumpsum	1		
64702	Archaeological Monitoring, NRHP Evaluation and Report, at	Lumpsum	1		
64703	Burial Recovery and Treatment Plan, at	Each	5		
SUB-TOTAL					\$

SUMMARY OF BID

a. Total Bid -----	\$
b. Either furnish foreign steel not to exceed minimal amount (Insert "0") or furnish foreign steel in excess of minimal amount (insert 25% x a) -----	\$
c. Sub-total -----	\$
d. Amount for comparison of bid -----	\$

NOTE:

Bidders must complete items "a" through "d" including the Project Completion Time, in calendar days. The Project Completion Time shall not exceed the maximum specified in Subsection 108.01 (c) - COMMENCEMENT

Completion Time shall not exceed the maximum specified in Subsection 108.01 (c) - COMMENCEMENT PROCECUTION, AND COMPLETION OF WORK.

Bidders must complete all unit prices and amounts. Failure to do so may be grounds for rejection of bid.