

SECTION 608 PAVED WATERWAYS

608.01 **DESCRIPTION** – Revised the text of this subsection to read as follows:

This work consists of constructing a concrete paved waterway, valley gutters or swales where indicated on the plans.

608.02 **MATERIAL** – Delete the text of this subsection and substitute the following:

- a. Bed Course - Bed course shall be compacted coral base conforming to subsection 301.02.B.
- b. Concrete - Concrete and materials for concrete, reinforcing steel, formwork, and joint filler shall conform to Section 601.
- c. Sub-base and Backfill. Backfill and sub-base material shall be compacted coral sub-base conforming to subsection 301.02.A.

CONSTRUCTION REQUIREMENTS

608.03 **GENERAL** – Revise this subsection as follows:

Perform excavation and backfill work under Section SCR 209. Place and compact the bed course to the thickness indicated on the plans. Compact each layer of base course material to not less than 95 percent of its maximum dry density and check field- in-place density as specified in Section SCR 209.

608.07 **CONCRETE PAVED WATERWAYS** - Add the following text to this subsection:

Construct and cast the concrete paved waterway, valley gutter or swale to the width, thickness, and slope indicated on the plans and in accordance with Section SCR 601. Place and secure the reinforcement in accordance with Section SCR 601.

608.11 **MEASUREMENT** – Delete the text of this subsection and substitute the following:

Measure concrete swale by the linear foot, in place, including excavation, bedding, concrete, and backfill work.

608.12 **PAYMENT** – Add the following text to this subsection:

Payment will be made under:

Pay Item No.	Pay item	Pay Unit
60801(A)	Concrete Swale, 6" thick at Driveway complete-in-place	Linear Foot
60801(B)	Concrete Swale, 4" thick at Driveway complete-in-place	Linear Foot
60801(C)	Grass Swale, complete-in-place	Linear Foot
60801(D)	Earth Channel, complete-in-place	Linear Foot

END OF SECTION 608