

BID SCHEDULE

Bidders Please Note: Before completing the Bid Schedule and Preparing the Proposal, carefully read "**Invitation to Bid**" and "**Notice to Bidders**", "**Instructions to Bidders**", "**Section 102 and Section 103**" of the Special Provisions of the Specifications.

The bidder shall state (in ink or type written) the bid price in words per unit measurement in the space provided in the Bid Schedule for every item for which a quantity is given.

The bidder shall also insert a unit bid price opposite each pay item name for which an estimated quantity appears in the Bid Schedule. A unit bid price is not to be entered nor tendered for any pay item for which no estimated quantity appears. Whenever a contingent amount is shown for any item in the **Bid Schedule**, such amount shall govern and be included in the bid total.

Basis of award of the bid shall be as described in Notice to Bidders, Instructions to Bidders, and Section 102 of the Special Provisions of the Specifications.

Pay Item Number bold ***Italics*** denote Major Item. (See Subsection 109.06 – Pricing of Adjustments)

BID SCHEDULE

I. ROUTE 38 (CHALAN GALAIDE) IMPROVEMENTS

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
15201	Construction Survey and Staking, at	Lump Sum	1		
15701	Soil Erosion Control, at	Lump Sum	1		
20101	Clearing and Grubbing, at	Acre	1.5		
20102(A)	Removal of Existing Trees, at	Each	17		
20303	Removal of Existing Traffic Sign, at	Each	1		
20401	Roadway Excavation (Cut), at	Cubic Yard	1,010		
20403	Roadway Embankment Construction (Fill), at	Cubic Yard	2,645		
SUB-TOTAL					\$

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
20404	Ponding Basin, (PB-3 & PB-4 including 12-inch-thick manufactured sand, 18-inch dia. HDPE pipe, riprap and all appurtenances) complete-in-place, at	Lump Sum	1		
25801	Reinforced Concrete Retaining Wall, Complete-in-place, includes base, sub-base preparation, and embankment fill., at	Cubic Yard	708		
30101 (A)	New Coral Aggregate Base, 8-inch depth, complete-in-place, at	Square Yard	2,970		
30102	New Coral Aggregate Sub-base, 12-inch depth, complete-in-place, at	Square Yard	2,970		
40201(A)	Hot Asphalt Concrete Pavement, 3-inch thick, Class "A" Grading "C" Type IV smoothness, at	Square Yard	2,918		
40201(B)	Hot Asphalt Concrete Pavement, 2- inch thick, Class "A" Grading "C" Type IV smoothness, at	Square Yard	110		
406A01	Dense Graded Anti-skid Asphalt Pavement, 1-inch thick, Grading "E", at	Square Yard	2,918		
41101	Asphalt Prime Coat, Grade SS-1H, at	Square Yard	2,918		
41201	Asphalt Tack Coat, Grade SS-1H, at	Square Yard	2,918		
60101	Reinforced Concrete Headwall, complete-in-place, at	Each	4		
60201(A)	18-inch diameter HDPE Corrugated Pipe, Type S, N-12, installed, at	Linear Foot	825		
SUB-TOTAL					\$

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
60201(B)	24-inch diameter HDPE Corrugated Pipe, Type S, N-12, installed, at	Linear Foot	40		
60402(A)	Side Inlet Catch Basin (SICB) including Grate, complete-in-place, at	Each	8		
60402(B)	Drainage Manhole, including frame and cover, complete-in-place, at	Each	1		
60801(B)	Concrete Swale, 4-inch thick, complete-in-place, at	Linear Foot	1,030		
60801(D)	Earth Channel, complete-in-place, at	Linear Foot	260		
60902	Concrete Curb, complete-in-place, at	Linear Foot	698		
60903	Scour Protection, complete-in-place, at	Linear Foot	30		
61102(B)	Water Manhole Cover Adjustment, complete-in-place, at	Each	1		
61104(C)	Realignment of Existing 2-inch Waterline, complete-in-place, at	Linear Foot	160		
63101(A)	Relocate Existing Power Poles Including Lines and Appurtenances, complete-in-place, at	Each	1		
63101(B)	Relocate Existing Guy Wire, including appurtenances, complete-in-place, at	Each	1		
63101(C)	Relocate Existing Telephone Pedestal including appurtenances, complete-in-place, at	Each	1		
SUB-TOTAL					\$

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
63301	Traffic Sign, Type 1, complete-in-place, at	Each	6		
63401	Pavement Marking, Type H, 4-inch wide, White or Yellow, at	Linear Foot	5,260		
63402	Pavement Marking, Type H, 12-inch wide, White, at	Linear Foot	12		
63501	Temporary Traffic Control, at	Lump Sum	1		
64701	Archaeological Work Plan, Testing and Report of Findings, Complete, at	Lumpsum	1		
64702	Archaeological Monitoring, NRHP Evaluation and Report, at	Lumpsum	1		
64703	Burial Recovery and Treatment Plan, at	Each	2		
SUB-TOTAL					\$
TOTAL BID AMOUNT (CHALAN GALAIDE IMPROVEMENTS)					

II. CHALAN GALAIDE WATERLINE REPLACEMENT

PAY ITEM NO.	DESCRIPTIONS (WITH UNIT BID IN WORDS)	UNIT	EST'D QTY	UNIT BID PRICE	BID AMOUNT
1	Mobilization/Demobilization	Lumpsum	1		
2	Pressure testing/chlorination	Lumpsum	1		
3	Removal and Disposal of Existing PRV	Lumpsum	1		
4	Connection to Existing 6-inch waterline	Lumpsum	1		
5	Cut and Cap New 6-inch waterline	Lumpsum	1		
6	New Waterline Crossing Over/Under Storm Drain Pipe	Each	7		
7	6-inch PVC Waterline Installation	Linear Feet	1,321		
8	2-inch Service Lateral Stub-out Installation (Detail 4/C-5)	Each	6		
9	Installation of Underground PRV Assembly	Lumpsum	1		
10	New Water Sample Tap Installation	Each	1		
11	Flowable fill	Cubic Yard	24		
SUB-TOTAL					\$
TOTAL BID AMOUNT (WATERLINE REPLACEMENTS)					

SUMMARY OF BID

a. Total Bid (Chalan Galaide Improvements & Waterline Replacements) -----	\$
b. Either furnish foreign steel not to exceed minimal amount (Insert "0") or furnish foreign steel in excess of minimal amount (insert 25% x a) -----	\$
c. Sub-total -----	\$
d. Amount for comparison of bid -----	\$

NOTE:

Bidders must complete items "a" through "d" including the Project Completion Time, in calendar days. The Project Completion Time shall not exceed the maximum specified in Subsection 108.01 (c) - COMMENCEMENT

Completion Time shall not exceed the maximum specified in Subsection 108.01 (c) - COMMENCEMENT
PROCECUTION, AND COMPLETION OF WORK.

Bidders must complete all unit prices and amounts. Failure to do so may be grounds for rejection of bid.